BHADRAVATI FOREST DIVISION.

Notification dated 22nd February 1924.

It is hereby notified for general information that a teak pole measuring 16 feet long and and 2'—4" in girth lying in the field of one Rudregowdana Mahadevanna of Lakshmisagara village, Tarikere Taluk. The log does not bear any departmental or property marks and is now under the custody of Patel Gangappa of the village. Any person having any right thereto is directed to present to the District Forest Officer, Bhadravati Division, within a month from the date of publication of this notification, a written statement of his claims and establish his rights thereto, failing which the ownership of the said piece shall under Section 42, Mysore Forest Regulation, vest in Government free from all encumbrances.

M. MACHAIYA,
District Forest Officer.

ENGINEERING DEPARTMENT.

SPECIAL WATER-SUPPLY CONSTRUCTION DIVISION.

Dated 11—16th February 1924.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Special Water-Supply Construction Division, up to 12 noon of 14th March 1924, for laying the Distribution System of Chikmagalur Water-Supply. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1924.

2. The plans and conditions may be seen at the Executive Engineer's office at Bangalore, on all working days between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Any tender furnishing rates for units other than those specified in the accompanying statement will not be considered.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash, or Government Promissory Notes, as earnest money, and be superscribed, "Tender for laying the Distribution System of Chikmagalur Water-supply in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement of works connected with Improvemens to the Distribution System of Water Supply to Chikmagalur Town.

No.	Details of work	Contents
1	Excavating, removing, cleaning, conveying and stacking the 4" Cast Iron Pipes from the Old Delivery Main to the site of works with refilling of the trench and reforming the road surface cut up.	15,840 Rft.
2	Excavating, removing, cleaning, conveying and stacking 6" Cast Iron Pipes from existing disribution and from old filter beds to the town with refilling and tamping of the trench and reforming the road surface cut up.	6,645 do
3	Excavating, removing, cleaning and conveying the existing old useful pipes (galvanised) to site of works in the town with refilling and tamping the trench and reforming the road surface cut up.	....
	(a)	1,230 of 2" Rft.
	(b)	420 of 1½" do
	(c)	1,422 of 1" do
	(d)	652 of ¾" do

No.	Details o work	Contents
4	Exavating and refilling the trench with tamping and remetalling cut up portions of road for laying pipe line.	3,450 Cyds.
5	Excavating and refilling and tamping the trench 1½′ x 1½′ with remetalling cut up portions of road after laying and jointing galvanised pipes, fixing specials and cocks with cuts, threads carting, etc., complete,	
	(a) 2″ galvanised pipes	5,715 Rft.
	(b) 1½″ do	7,341 do
	(c) 1″ do	8,511 do
	(d) ¾″ do	1,435 do
6	Excavating and refilling the trench after removing, conveying and stacking old useless galvanised pipes of 1″ to ¾″ sizes, pipes to be stacked at the Municipal store yard.	5,168 do
7	Removing, conveying and stacking old useless galvanised pipes 1″ to ¾″ from site to Municipal Store yard.	9,124 do
8	Laying and cement jointing of 6″ C. I. pipes with cuts, collar joints, etc., complete including fixing specials.	120 joints each
9	Laying and lead jointing of 6″ C. I. pipes with cuts collar joints, etc., complete including joints at valves, specials and fixing specials, etc.	136 do
10	Laying and cement jointing of 4″ C. I. pipes with cuts, collar joints, etc., complete, with fixing specials.	400 do
11	Laying and lead jointing of 4″ C. I. pipes with cuts, collar joints and fixing specials, etc., complete.	472 do
12	Laying and cement jointing of 2½″ C. I. pipes with carting to site, cuts collar joints, etc., complete.	94 do
13	Laying and lead jointing of 2½″ C. I. pipes with carting to site cuts, collar joints and fixing specials included.	50 do
14	Fixing C. I. valves after overhauling them with 1/8″ to 3/16″ rubber insertions, packings, bolts, nuts, etc., complete 6″.	2 do
15	Do do do complete 4″	6 do
16	Do do do complete 2½″	1 do
17	Do do do air valve on 6″ Main	1 do
18	Do do do on 4″ Sub Main	1 do
19	Do do do on 2½″ Sub Main	1 do
20	Do do do 4″ scour valve	2 do
21	Fixing W. I. Flap shutters 2½′ x 2½′ with C. I. frames with four bed bolts, lead joints on stone slabs and cement grouting in brick work, complete	12 do
22	Fixing C. I. Road boxes, over gland cock cisterns 1½′ x 1½′ square with cost of cistern, etc., included.	95 do
23	Main borings (a) ¾″	30 do
	(b) 1″	10 do
	(c) 1½″	6 do
	(d) 2″	2 do
24	VALVE CISTERNS AND PUBLIC FOUNTAINS.	
	Earthwork excavatioa	72 C. yds.
	Concrete in surki mortor	612 C. ft.
	Burnt brick in surki mortor	672 do
	Burnt stone slabs finely dressed and fixed in mortor	1,152 S. ft.
	½″ cement plastering (1 to 3)	1·80 Sqrs.
	Cement pointing	11·2 do
	Chunam plastering	3·60 do
	Constructing cement drains	324 R. ft.
	Burnt stone slabs 6″ thick. One line dressed and put up	81 Sft.
	Fixing the cast iron fountains with bolts and nuts	36 No.
	Gravelling all round the platform to a width of 1½′	36 No.

Notification dated 18th February 1924.

It is hereby notified for the information of the public that stores enumerated in the statement hereunder will be sold by public auction on 14th March 1924 at Bangalore at the Stores of Special Water Construction Division in the compound of Special Water-Supply Construction Division.

2. The materials selected for the sale will be available at the site for examination on the previous day with the permission of the Assistant Engineer, who will be at the spot.

3. The terms and conditions of the sale are:—

(a) that the article or articles will be knocked down to the highest bidder and that in the event of any dispute arising between two or more bidders at the same price, the article or articles will be put up again and resold.

(b) that all the articles purchased shall be at the risk of the purchaser thereof, from the time of the sale.

(c) that all articles should be removed with faults and errors of all description as sold.

(d) that cash should be paid in full for article or articles purchased by bidders before delivery, but that the articles will not be allowed to be removed from the place of auction until after close of sale.

(e) that in case of default of the payment of the whole or any portion of the purchase amount due by any bidder, the articles will be resold and the bidder will be liable to any loss incurred thereby.

(*f*) that a deposit of 10 per cent of the amount will be made by the successful bidder, immediately the articles are knocked down in his favour, and that such deposits shall be treated as forfeited to Government in case of any default to pay the purchase money within the time prescribed in clause (*g*), also that on resale as laid down in clause (c), the bidder will be liable to make good any loss incurred thereby, without having the right to participate in any excess realised.

(*g*) that the purchased money should be paid up within three days from the date of sale and that the articles purchased should be removed immediately thereafter.

(*h*) that the sale shall be subject to confirmation by the Executive Engineer.

List of Auction Sale of Stores.

No.	Description of articles	Number of quantity
	OFFICE FURNITURE.	
1	Almiarahs teak wood	2
2	Teakwood tables with drawers	2
3	Lantern Dietz	1
4	Seals ordinary	1
5	Iron Commode	1
	TOOLS	
1	Axes felling Country made	3
2	Axes Pick	9
3	Bottles for water	2
4	Chisel carpenters	2
5	Chisel flat	2
6	Files rough flat 14"	2
7	Files half round 14"	1
8	Do 12"	1
9	Feeder oil, tin ½ to 1 pint	3
10	File handle	1
11	Barrel deal wood empty	1
12	Hammer stone breaking	3
13	Locks lever brass of sizes	4
14	Locks brass Aligar	1
15	Miller Locks	3
16	Pans Mortor	2
17	Penknife	1
18	Hawk Saw with six blades	1
19	Kuja brass with tumbler	1
20	Mumties	3
	DRAWING AND MATHEMATICAL INSTRUMENTS.	
1	Link rod bamboos	10
2	Metallic tape 50' without case	7
3	Spirit level	1
	STOCK MATERIALS.	
1	4" x 4" S. W. Junction pipes	1
	SURPLUS MATERIALS.	
1	1" Gland cock	1
2	Manilla rope	2

H. F. MARKER,
Executive Engineer,
Special Water-Supply, Construction Division.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE SUPERINTENDENT, GOVERNMENT PRINTING IN MYSORE, BANGALORE.

FOR SALE.

Notice is hereby given for the information of the General Public that Framed Coloured Portraits of His Highness the Maharaja of Mysore are available for sale at Government Central Book Depot, Fort, Bangalore City, at Rs. 15 per copy. Intending purchasers may apply to the Curator of the Depot.

B. PUTTAIYA,
Superintendent.